



Floor

Schedule for Secondary School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
HS401 GENERAL LEARNING UNIT				
HS401.01	General Learning Space - Adjoining	FLOOR FINISH Carpet finish	-	-
HS401.02	General Learning Space with Independent Learning Area	FLOOR FINISH Carpet finish	-	-
HS401.07	General Learning Space - Divisible	FLOOR FINISH Carpet finish	-	-
HS401.03	Shared Learning Space with Practical Activities Area	FLOOR FINISH Carpet finish	-	-
HS401.04	Seminar Room- General	FLOOR FINISH Carpet finish	-	-
HS401.05	GLS Store Room	FLOOR FINISH ISF- Industrial Sheet Flooring	-	-
HS401.06	Practical Activities Area	FLOOR FINISH ISF- Industrial Sheet Flooring	-	-
HS402 SENIOR LEARNING UNIT				
HS402.01	Shared Study Space with Practical Activities Area	FLOOR FINISH Carpet finish	-	-
HS403.01	Senior Learning Centre with Practical Activities Area	FLOOR FINISH Carpet finish	-	-
HS404 SCIENCE LEARNING UNIT				
HS404.01	Science General Learning Space with Demonstration Bench	FLOOR FINISH Carpet finish (CP) with Industrial Sheet Floor (ISF) across front around Demonstration Bench.	-	-
HS404.10	Small Science General Learning Space	FLOOR FINISH Carpet finish	-	-



Floor

Schedule for Secondary School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
HS404.02	Shared Science Laboratory	FLOOR FINISH Industrial Sheet Flooring (ISF) including Safety Shower with falls to floor waste. Coved skirting to fixed benches.	-	-
HS404.03	Seminar Room - Lab/Workshop	FLOOR FINISH Carpet finish	-	-
HS404.04	Science Preparation	FLOOR FINISH Industrial Sheet Flooring (ISF) including Safety Shower with falls to floor waste. Coved skirting to fixed benches.	-	-
HS404.06	Apparatus Store Room	FLOOR FINISH CC-Steel Trowelled Finished Concrete	-	-
HS404.07	Apparatus Storage	FLOOR FINISH Industrial Sheet Flooring (ISF)	-	-
HS404.08	Chemical Store Room	FLOOR FINISH CC - Steel Trowelled Chemical Resistant Concrete Finish with Coved skirting to walls and graded towards acid bay.	-	-
HS404.09	Botany/Zoology Room	FLOOR FINISH CC - Steel Trowelled Chemical Resistant Concrete Finish graded to floor waste. Suitable for hosing out	-	-
HS405 VISUAL ARTS LEARNING UNIT				
HS405.01	Visual Arts General Learning Space	FLOOR FINISH Carpet finish (CP)	-	-
HS405.02	Visual Arts Learning Space with Art Trough	FLOOR FINISH Industrial Sheet Flooring (ISF)	-	-
HS405.03	Shared Visual Arts Workshop	FLOOR FINISH Industrial Sheet Flooring (ISF)	-	-
HS405.04	Visual Arts Store Room	FLOOE FINISH CC Steel Trowelled Concrete Finish	-	-
HS405.05	Visual Arts Project Store Room	FLOOE FINISH CC Steel Trowelled Concrete Finish	-	-
HS405.06	Dark Room	FLOOR FINISH Industrial Sheet Flooring (ISF) Electro-static doormat to light trap.	-	-



Floor

Schedule for Secondary School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
HS413.01	Materials Workshop	FLOOR FINISH Industrial Sheet Flooring (ISF)	-	FLOORS - OTHER Floor loading to take equipment
HS413.02	Project Store Room	FLOOR FINISH Steel Trowelled Concrete Finish	-	-
HS407 PERFORMANCE & FITNESS LEARNING UNIT				
HS406.01	Shared Health/PE & Performing Arts Workshop	FLOOR FINISH GUC- Carpet with sound impact absorptive underlay for dance activities.	-	-
HS406.02	Performing Arts Store Room	FLOOR FINISH Carpet finish (CP)	-	-
HS406.03	Seminar Room - Practice	FLOOR FINISH Carpet finish (CP)	-	-
HS407.02	PE & Fitness Store Room	FLOOR FINISH Industrial Sheet Flooring (ISF)	-	FLOOR - OTHER Ensure zero step threshold
HS407.04	General Learning Space - With Performance Area	FLOOR FINISH Carpet finish (CP)	-	-
HS408.01	Shared PE Fitness Laboratory with Wet Area	FLOOR FINISH GUC- Carpet with shock absorbing underlay. ISF - Industrial Sheet Flooring to sink area	-	FLOOR - OTHER ISF - Industrial Sheet Flooring to sink area
HS408.03	Change Room	FLOOR FINISH Ceramic Tiles (CT)	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Ensure floor is well graded to floor waste.
HS409 TAS MAT 1 - KITCHEN				
HS409.01	Food & Textile Technology General Learning Space with Kitchen Demonstration Bench	FLOOR FINISH Industrial Sheet Flooring (ISF)	-	FLOOR - OTHER Cove Sheet flooring at demonstration bench.
HS409.02	Food & Textile Technology General Learning Space with Sink	FLOOR FINISH Industrial Sheet Flooring (ISF)	-	-
HS409.03	Shared Domestic Kitchen	FLOOR FINISH Industrial Sheet Flooring (Safety Flooring) (ISF) with coved skirting to walls and benches	-	-



Floor

Schedule for Secondary School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
HS414.01	Semi-Commercial Kitchen	FLOOR FINISH Industrial Sheet Flooring (Safety Flooring) (ISF) with coved skirting to walls and benches	-	-
HS409.04	Kitchen - Store Room	FLOOR FINISH Industrial Sheet Flooring (ISF)	-	-
HS409.05	Kitchen - Preparation	FLOOR FINISH Industrial Sheet Flooring (ISF)	-	-
HS409.07	Pantry - Domestic	FLOOR FINISH Industrial Sheet Flooring (ISF)	-	-
HS414.02	Pantry - Semi-Commercial	FLOOR FINISH Industrial Sheet Flooring (ISF)	-	-
HS409.08	Laundry	FLOOR FINISH Ceramic Tiles (CT)	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Ensure floor is well graded to floor waste.
HS410 TAS MAT 2 - WOOD & METAL				
HS410.01	Wood & Metal Technology General Learning Space - With Sink	FLOOR FINISH CP - Carpet finish. ISF - Industrial Sheet Flooring to sink area	-	-
HS410.02	Wood & Metal Technology General Learning Space	FLOOR FINISH Industrial Sheet Flooring (ISF)	-	-
HS410.03	Shared Wood & Metal Workshop	FLOOR FINISH Industrial Sheet Flooring (ISF) Concrete (CC) to Finishing area and Welding/Hot metals area.	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Ensure floor is well graded to floor waste.
HS410.04	Wood & Metal Materials Store Room	FLOOR FINISH Steel trowel finish Concrete (CC)	-	-
HS410.05	Wood & Metal Project Store Room	FLOOR FINISH Steel trowel finish Concrete (CC)	-	-
HS410.06	Materials Learning Space - Wood & Metal	FLOOR FINISH Industrial Sheet Flooring (ISF)	-	FLOORS - OTHER Floor loading to take equipment

HS411 MULTIMEDIA LEARNING UNIT



Floor

Schedule for Secondary School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
HS411.01	Shared Multimedia Workshop	FLOOR FINISH CP - Carpet finish.	-	-
HS411.02	Multimedia Store Room	FLOOR FINISH CP - Carpet finish.	-	-
HS411.03	Multimedia Studio	FLOOR FINISH CP - Carpet finish.	-	-
HS412 LECTURE LEARNING UNIT				
HS412.01	Lecture Theatre	FLOOR FINISH CP - Carpet finish.	-	FLOOR - OTHER Floor to be partially raked.
HS412.02	Lecture Store Room	FLOOR FINISH CP - Carpet finish.	-	-
HS430 SPECIAL EDUCATION LEARNING UNIT (IO/IS/P)				
HS430.01	General Learning Space - IO	FLOOR FINISH CP - Carpet finish.	-	-
HS430.02	General Learning Space - IS/P	FLOOR FINISH CP - Carpet finish.	-	-
HS430.10	Shared Practical Activities Area - IO/IS/P	FLOOR FINISH Industrial Sheet Flooring (ISF)	-	-
HS430.20	GLS Store Room - IO/IS/P	FLOOR FINISH To match adjacent home base, CP - Carpet finish. Or Industrial Sheet Flooring, (ISF) if adjoining similar finish.	-	-
HS440 SPECIAL EDUCATION LEARNING UNIT (BD/CD/ED)				
HS440.01	General Learning Space - BD/CD/ED	FLOOR FINISH CP - Carpet finish.	-	-
HS440.10	Multipurpose Space - BD/CD/ED	FLOOR FINISH Industrial Sheet Flooring (ISF)	-	-



Floor

Schedule for Secondary School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
HS440.20	Project Store Room - BD/CD/ED	FLOOR FINISH Industrial Sheet Flooring (ISF)	-	-
HS450 SPECIAL EDUCATION LEARNING UNIT (TUTORIAL)				
HS450.01	Independent Learning Space - Tutorial	FLOOR FINISH CP - Carpet finish.	-	-
HS450.02	Tutorial Centre Seminar Room	FLOOR FINISH CP - Carpet finish.	-	-
HS501 LIBRARY				
HS501.01	Library Main Entry	FLOOR FINISH CP- Carpet finish, to match adjacent area.	-	-
HS501.03	Library Main Area	FLOOR FINISH CP - Carpet finish.	-	-
HS501.07	Printing/Photocopying Area	FLOOR FINISH CP - Carpet finish.	-	-
HS501.08	Seminar Room - Divisible	FLOOR FINISH CP - Carpet finish.	-	-
HS501.09	Library Administration	FLOOR FINISH CP - Carpet finish. Matt near sink	-	-
HS501.13	Computer Learning Space	FLOOR FINISH CP - Carpet finish.	-	-
HS501.14	Computer Store Room	FLOOR FINISH ASV- Antistatic Vinyl / Linoleum finish.	-	-
HS501.15	Senior Study	FLOOR FINISH CP - Carpet finish.	-	-
HS501.17	Careers Adviser's Office	FLOOR FINISH CP - Carpet finish.	-	-



Floor

Schedule for Secondary School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
HS501.18	System Administrator's Office	FLOOR FINISH CP - Carpet finish.	-	-
HS501.19	Communications Room	FLOOR FINISH ASV- Antistatic Vinyl / Linoleum finish.	-	-
HS502 MOVEMENT COMPLEX				
HS502.01	Gymnasium	FLOOR FINISH Sprung Timber Floor (TPS)	-	FLOOR - OTHER Floor to be permanently marked with: 50mm line markings for; Basketball (Yellow), Netball (Green), Volleyball (Red).
HS502.03	Gymnasium - Extension	FLOOR FINISH Sprung Timber Floor (TPS)	-	-
HS502.18	Gymnasium - Half Court	FLOOR FINISH Sprung Timber Floor (TPS)	-	FLOOR - OTHER Floor to be permanently marked with: 50mm line markings for; Basketball (Yellow), Volleyball (Red). Drainage outlet required under sprung floor.
HS502.04	Movement Studio	FLOOR FINISH Sprung timber floor(TPS) to flat floor area, Carpet (CP) to tiered area.	-	-
HS502.05	Sports Equipment Store Room	FLOOR FINISH Steel Trowel finish Concrete (CC)	-	FLOOR - OTHER Ensure no step at threshold for movement of equipment.
HS502.06	Large Equipment Store Room	FLOOR FINISH Steel Trowel finish Concrete (CC)	-	FLOOR - OTHER Ensure no step at threshold for movement of equipment.
HS502.07	Outdoor Equipment Store Room	FLOOR FINISH Steel Trowel finish Concrete (CC)	-	-
HS502.08	Chair Store Room	FLOOR FINISH Steel Trowel finish Concrete (CC)	-	FLOOR - OTHER Ensure no step at threshold for movement of chairs.
HS502.10	Movement Studio Store Room	FLOOR FINISH Industrial Sheet Flooring (ISF)	-	FLOOR - OTHER Ensure no step at threshold for movement of chairs.
HS502.11	Control Room	FLOOR FINISH CP - Carpet finish.	-	-
HS502.12	First Aid	FLOOR FINISH Industrial Sheet Flooring (ISF)	-	-



Floor

Schedule for Secondary School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
HS502.13	Shower	FLOOR FINISH CT - Ceramic Tiles graded to falls.	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	-
HS502.15	Staff Shower	FLOOR FINISH CT - Ceramic Tiles graded to falls.	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	-
HS502.16	Stage	FLOOR FINISH Timber Floor (TP)	-	-
HS502.17	Demountable Platform	-	-	-
HS503 OUTDOOR COVERED WORKSHOP				
HS503.01	Shared Outdoor Covered Workshop	FLOOR FINISH CC - Steel Trowel Concrete graded with falls to grated drain.	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	-
HS503.06	Outdoor Covered Workshop	FLOOR FINISH CC - Steel Trowel Concrete graded with falls to grated drain.	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	-
HS503.02	Welding/Hot Metals Area	FLOOR FINISH CC - Steel Trowel Concrete .	-	-
HS503.03	Kiln Space	FLOOR FINISH CC - Steel Trowel Concrete .	-	-
HS503.04	LPG Store Room	FLOOR FINISH CC - Steel Trowel Concrete .	-	-
HS503.05	Pottery Store Room	FLOOR FINISH CC - Steel Trowel Concrete .	-	-
HS504 OUTDOOR LEARNING				
HS504.01	Outdoor Learning Space	FLOOR FINISH General paving	-	FLOOR - OTHER Ensure adequate drainage away from seating area to remove surface water
HS504.02	Tiered Outdoor Learning Space	FLOOR FINISH General paving	-	FLOOR - OTHER Ensure adequate drainage away from seating area to remove surface water



Floor

Schedule for Secondary School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
HS504.03	Outdoor Learning Space - Small Group	FLOOR FINISH General paving	-	FLOOR - OTHER Ensure adequate drainage away from seating area to remove surface water
HS505 GAMES				
HS505.01	Games Court	FLOOR FINISH A resilient, non-slip, low maintenance and antiglare surface is required such as Asphaltic concrete	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER 50mm line markings for; Basketball(yellow), Netball(Green), Volleyball(Red) and Tennis(White). Ensure adequate drainage to perimeter of court, to remove surface water.
HS505.03	Games Field	FLOOR FINISH Area turfed including spectator bank .	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Provide adequate drainage on in playing field
HS505.04	Batting Practice Nets	FLOOR FINISH Concrete Pitch with bituminous covering. Area surrounding pitch to be grass.	-	FLOOR - OTHER Provide adequate drainage pitch area
HS506 AGRICULTURE				
HS506.01	Agriculture Shed Workshop	FLOOR FINISH Concrete Floor - (C)	-	-
HS506.02	Agriculture Tools Storage	FLOOR FINISH CC - Steel Trowel Concrete .	-	FLOOR - OTHER Grade floor to outside for drainage
HS506.03	Animal Space	FLOOR FINISH CC - Steel troweled Concrete floor well graded to enable hosing out.	-	FLOOR - OTHER Grade floor to perimeter dish drain
HS506.04	Plant Space	FLOOR FINISH CC - Steel troweled Concrete floor well graded to enable hosing out.	-	FLOOR - OTHER Grade floor to perimeter dish drain
HS506.05	Covered Area - Agriculture	FLOOR FINISH CC - Steel troweled Concrete floor well graded to enable hosing out.	-	FLOOR - OTHER Grade floor to outside for drainage
HS506.06	Agriculture Plot	FLOOR FINISH 10m x10m Hard Standing surface area (eg Road base)	-	-

HS601 ADMINISTRATION UNIT



Floor

Schedule for Secondary School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
HS601.01	Public Reception	FLOOR FINISH CP - Carpet finish.		
HS601.03	Student Reception	FLOOR FINISH CP - Carpet finish.		
HS601.05	Student Waiting	FLOOR FINISH CP - Carpet finish.		
HS601.06	Principal's Office / Meeting Room	FLOOR FINISH CP - Carpet finish.		
HS601.07	Deputy Principal's Office	FLOOR FINISH CP - Carpet finish.		
HS601.08	Interview Room / Office	FLOOR FINISH CP - Carpet finish.		
HS601.09	Interview Room / Meeting	FLOOR FINISH CP - Carpet finish.	-	
HS601.11	Administration - Clerical	FLOOR FINISH CP - Carpet finish.	-	
HS601.14	Administration- Executive	FLOOR FINISH CP - Carpet finish.	-	
HS601.17	Store Room	FLOOR FINISH Industrial Sheet Flooring (ISF)	-	
HS601.18	Clinic	FLOOR FINISH Industrial Sheet Flooring (ISF)	-	
HS601.21	Visitor's Office	FLOOR FINISH CP - Carpet finish.	-	
HS601.22	Tea Room	FLOOR FINISH Industrial Sheet Flooring (ISF)	-	
HS601.23	Utility Space	FLOOR FINISH CP - Carpet finish.	-	



Floor

Schedule for Secondary School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
HS601.81	Entrance Zone	-	-	-
HS602 STAFF UNIT				
HS602.01	Staff Study	FLOOR FINISH CP - Carpet finish.	-	-
HS602.04	Staff Lounge	FLOOR FINISH CP - Carpet finish. ISF - Industrial sheet flooring to Kitchen area.	-	-
HS602.08	Preparation/Printing	FLOOR FINISH ISF - Industrial sheet flooring to Kitchen area.	-	-
HS602.11	Staff Toilet	FLOOR FINISH CT - Ceramic Tiles,	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Coved Skirting and floor graded with falls to flow waste
HS602.12	Access Shower/Toilet	FLOOR FINISH CT - Ceramic Tiles,	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Coved skirting tiles at wall Falls to floor waste. Tiles are not to have a bevelled edge. Tiling to have flush joints. Avoid abrupt changes in level.
HS603 STUDENT SERVICES UNIT				
HS603.01	Toilets	FLOOR FINISH CT - Ceramic Tiles,	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Coved skirting tiles at wall Well graded falls to floor waste.
HS603.02	Drinking Facilities	FLOOR FINISH Water Resistant including adjacent area. Drinking Troughs not to be located in carpeted areas.	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER falls to surface drainage if external. Falls to floor waste if internal
HS603.03	Seating	FLOOR FINISH Paved Surface	-	-
HS603.04	Hand Washing Outlets	-	-	-
HS603.06	Access Shower/Toilet/Change	FLOOR FINISH CT - Ceramic Tiles,	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Coved skirting tiles at wall Falls to floor waste. Tiles are to have flush joints and not to have a bevelled edge. Avoid abrupt changes in level.



Floor

Schedule for Secondary School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
HS603.09	Laundry	FLOOR FINISH CT - Ceramic Tiles,	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Coved skirting tiles at wall Falls to floor waste. Tiles are to have flush joints and not to have a bevelled edge. Avoid abrupt changes in level.
HS604 CANTEEN				
HS604.01	Canteen	FLOOR FINISH ISF - Industrial sheet flooring(Safety floor).	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Coved skirting to floor at wall and plinths. Solid plinth under benches Falls to floor waste located adjacent to bench.
HS604.04	Canteen Office/Store Room	FLOOR FINISH ISF - Industrial sheet flooring(Safety floor).		FLOOR - OTHER Coved skirting to floor at wall.
HS604.07	Vending Machines	FLOOR FINISH CC - Steel troweled Concrete floor.		-
HS605 STORAGE UNIT				
HS605.01	Archive Store Room	FLOOR FINISH CC - Steel troweled Concrete floor.		-
HS605.03	Garden Store Room	FLOOR FINISH CC - Steel troweled Concrete floor.		FLOOR - OTHER threshold to be flush finished to enable wheeled equipment.
HS605.04	Bulk Store Room	FLOOR FINISH CC - Steel troweled Concrete floor.		FLOOR - OTHER threshold to be flush finished to enable wheeled equipment etc.
HS605.05	Cleaning Supplies Store Room	FLOOR FINISH CC - Steel troweled Concrete floor.	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER threshold to be flush finished to enable wheeled equipment etc. Grade floor to floor waste where provided
HS605.06	Cleaning Distributed Store Room	FLOOR FINISH ISF - Industrial sheet flooring.	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER threshold to be flush finished to enable wheeled equipment etc. Grade floor to floor waste where provided
HS606 COVERED OUTDOOR SPACE				
HS606.01	Covered Outdoor Space	FLOOR FINISH Paved Area	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Ensure adequate surface drainage of the area.
HS607 ASSEMBLY COURT				



Floor

Schedule for Secondary School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
HS607.01	Quadrangle	FLOOR FINISH Broom finished coloured concrete to reduce glare.	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Ensure adequate surface drainage of the area.
HS607.02	Flagpole	FLOOR FINISH Paved Area		-
HS607.21	Assembly Zone	-		-
HS608 PEDESTRIAN CIRCULATION				
HS608.01	Paved Areas	FLOOR FINISH Broomed, coloured concrete to reduce glare; unit paving around trees (gravel is not to be used)		-
HS608.02	Paved Access	FLOOR FINISH Broom finished concrete		FLOOR - OTHER Areas to be graded to provide drainage while maintaining wheelchair accessible grades
HS609 VEHICULAR CIRCULATION				
HS609.01	Service Roads	FLOOR FINISH Service Road (heavy Duty) - reinforced concrete Service Roads (Light Duty) - road metal base with bitumen flush seal Service Road (Access) - road metal base with bitumen flush seal	-	FLOOR - OTHER Heavy Duty Service Roads - Drainage to swale and perimeter sub soil drains or kerb and gutter with piped stormwater drains for poor soil conditions (CBR<5). Light Duty Service Roads - Kerb and gutter and stormwater drainage as necessary.
HS609.04	Bulk Waste Pad	FLOOR FINISH Reinforced concrete slab		-
HS609.05	Car Parking	FLOOR FINISH Asphaltic concrete on base course or reinforced concrete broomed finish.	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Drainage to swale and perimeter subsoil drains, or Kerb and Gutter with piped stormwater drains for poor soil conditions (CBR<5). Monograde with lower side being the longer side is preferred option. Where slope is between 1:50 and 1:30 drain to centre preferred.
HS609.06	Bus Zone	FLOOR FINISH Heavy duty reinforced concrete or asphaltic concrete.	-	FLOOR - OTHER Kerb and Gutter with piped stormwater drains
HS609.07	Bicycle Enclosure	FLOOR FINISH Student Waiting Zone: Broomed and coloured concrete.	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Where slope is between 1:50 and 1:30 drain to centre preferred.



Floor

Schedule for Secondary School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
HS609.08	Crossovers	FLOOR FINISH Reinforced concrete slab to local council requirements	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Stormwater drainage as required
HS610 OPEN SPACES				
HS610.01	Open Space	FLOOR FINISH Grass	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Preferred slope 1:8 and 1:4 maximum.
HS610.11	Street Frontage Zone	-	-	FLOOR - OTHER Massed plantings on slopes between 1:4 and 1:3. Slopes >1:3 may require retaining walls.
HS610.12	Active Zone	-	-	-
HS610.13	Passive Zone	-	-	-
HS610.14	Boundary Zone	-	-	-
HS610.15	Out of Bounds Zone	-	-	-
HS610.16	Special Function Zone	-	-	-
HS611 SERVICES				
HS611.01	Dust Extraction Space	FLOOR FINISH CC - Steel troweled Concrete floor.	-	FLOOR - OTHER Provide fall to door for drainage
HS610.17	Services Zone	-	-	-
HS611.02	Main Switchroom	-	-	-
HS611.03	Distribution Board Cupboard	-	-	-
HS612 SITE				
HS612.01	Fencing	-	-	-
HS612.03	Waste Recycling	-	-	-
HS612.04	Signs	-	-	-
HS612.05	Site	-	-	-