



Floor

Schedule for Primary School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
PS401 HOME BASE UNIT				
PS401.01	Home Base with Practical Activities Area	FLOOR FINISH Carpet finish	-	-
PS401.11	Home Base Store Room	FLOOR FINISH Carpet to match Home Base or industrial sheet flooring	-	-
PS401.21	Withdrawal Room	FLOOR FINISH Carpet finish	-	-
PS401.22	Shared Withdrawal Room	FLOOR FINISH Carpet finish	-	-
PS401.31	Practical Activities Area	FLOOR FINISH Industrial sheet flooring	-	-
PS401.32	Shared Practical Activities Area	FLOOR FINISH Industrial sheet flooring	-	-
PS401.41	Personal Effects Storage	FLOOR FINISH Industrial sheet flooring	-	-
PS430 SPECIAL EDUCATION LEARNING UNIT - IO/IS/P				
PS430.01	Home Base with Practical Activities Area - IO	FLOOR FINISH Carpet finish	-	-
PS430.02	Home Base with Practical Activities Area - IS/P	FLOOR FINISH Carpet finish	-	-
PS430.11	Home Base Store Room - IO/IS/P	FLOOR FINISH Carpet to match Home Base or industrial sheet flooring if store opens onto similar floor material	-	-
PS430.21	Withdrawal Area - IO/IS/P	FLOOR FINISH Carpet finish	-	-
PS430.22	Shared Withdrawal Room - IO/IS/P	FLOOR FINISH Carpet finish	-	-
PS430.31	Practical Activities Area - IO/IS/P	FLOOR FINISH Industrial sheet flooring	-	-
PS430.32	Shared Practical Activities Area - IO/IS/P	FLOOR FINISH Industrial sheet flooring	-	-
PS430.41	Personal Effects Storage - IO/IS/P	FLOOR FINISH Industrial sheet flooring	-	-
PS440 SPECIAL EDUCATION LEARNING UNIT - BD/CD/ED				
PS440.01	Home Base with Practical Activities Area - BD/CD/ED	FLOOR FINISH Carpet finish	-	-
PS440.31	Practical Activities Area - BD/CD/ED	FLOOR FINISH Industrial sheet flooring	-	-
PS501 LIBRARY UNIT				
PS501.01	Library Main Area - Small	FLOOR FINISH Carpet finish	-	-
PS501.03	Library Main Area - Large	FLOOR FINISH Carpet finish	-	-
PS501.11	Office / Workroom	FLOOR FINISH Carpet finish	-	FLOOR - OTHER Mat near sink
PS501.12	Shared Office / Workroom	FLOOR FINISH Carpet finish	-	FLOOR - OTHER Mat near sink



Floor

Schedule for Primary School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
PS501.21	Communications Room	FLOOR FINISH Anti-static vinyl/Linoleum	-	-
PS501.31	KLA Resource Store Room	FLOOR FINISH Industrial sheet flooring	-	-
PS502 SPECIAL PROGRAMS UNIT				
PS502.01	Special Programs Room	Carpet finish	-	-
PS502.03	Special Programs Store Room	FLOOR FINISH Carpet finish	-	-
PS503 COMMUNAL HALL UNIT				
PS503.01	Communal Hall - Small	FLOOR FINISH Sprung timber floor	-	-
PS503.02	Communal Hall - Large	FLOOR FINISH Sprung timber floor	-	-
PS503.11	Chair Store Room	FLOOR FINISH Steel troweled concrete	-	-
PS503.21	PE Store Room	FLOOR FINISH Steel troweled concrete	-	-
PS503.31	Sports Store Room	FLOOR FINISH Steel troweled concrete	-	-
PS503.41	Performance Store Room	FLOOR FINISH Steel troweled concrete	-	-
PS503.51	Sound Cupboard	FLOOR FINISH Steel troweled concrete	-	-
PS504 COVERED OUTDOOR LEARNING AREA (COLA)				
PS504.01	Covered Outdoor Learning Area (COLA)	FLOOR FINISH Paving generally. Central area to be relatively flat	-	FLOOR - OTHER Central area is to be kept dry during wet weather, no water collection, drains or sumps within that area. Surface water collection to be kept to the periphery.
PS504.03	Covered Outdoor Space	FLOOR FINISH Paving generally. Central area to be relatively flat	-	FLOOR - OTHER Central area is to be kept dry during wet weather, no water collection, drains or sumps within that area. Surface water collection to be kept to the periphery.
PS505 GAMES UNIT				
PS505.01	Games Court	FLOOR FINISH Asphaltic concrete preferred for resilience, non-slip, low maintenance and non-glare.	-	-
PS506 KILN UNIT				
PS506.01	Kiln Room	FLOOR FINISH Steel troweled concrete	-	-
PS601.01	Entry Vestibule	FLOOR FINISH Carpet finish	-	-
PS601.11	Principal's Office	FLOOR FINISH Carpet finish	-	-
PS601.12	Principal / Meeting Room	FLOOR FINISH Carpet finish	-	-



Floor

Schedule for Primary School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
PS601.13	Deputy Principal's Office	FLOOR FINISH Carpet finish	-	-
PS601.14	Deputy Principal - Double Office	FLOOR FINISH Carpet finish	-	-
PS601.15	Interview Room / Office	FLOOR FINISH Carpet finish	-	-
PS601.16	Interview Room	FLOOR FINISH Carpet finish	-	-
PS601.21	Clerical / Printing	FLOOR FINISH Carpet finish	-	-
PS601.23	Clerical/Printing/Workroom	FLOOR FINISH Carpet finish	-	-
PS601.41	Security Store Room	FLOOR FINISH Industrial sheet flooring	-	-
PS601.51	Sick Bay	FLOOR FINISH Industrial sheet flooring	-	-
PS601.71	Community Clinic	FLOOR FINISH Carpet floor finish with industrial sheet flooring at sink and ceramic tiles in toilets	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	-
PS601.81	Entrance Zone	-	-	-
PS602 STAFF UNIT				
PS602.01	Staff Room	FLOOR FINISH Carpet floor finish with industrial sheet flooring at sink and bench.	-	FLOOR - OTHER Industrial Sheet Flooring in front of sink & bench
PS602.03	Staff Room - Adjoining Annexe	FLOOR FINISH Carpet floor finish with industrial sheet flooring at sink and bench.	-	FLOOR - OTHER Industrial Sheet Flooring in front of sink & bench
PS602.11	Staff Toilet	FLOOR FINISH Ceramic tiled floor finish	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Waterproofed floor with coved skirting; floor waste with falls in floor.
PS602.12	Access Shower/Toilet	FLOOR FINISH Ceramic tiled floor finish (tile joints be flush)	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Waterproofed floor with coved skirting; floor waste with falls in floor.
PS602.21	Staff Room Annexe	FLOOR FINISH Carpet finish	-	-
PS603 STUDENT AMENITIES				
PS603.01	Toilets	FLOOR FINISH Ceramic tiled floor finish	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Coved skirting for easy cleaning.
PS603.03	Drinking Facilities	-	-	-
PS603.04	Hand Washing Outlets	-	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	-
PS603.05	Seating	FLOOR FINISH Paved area	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Falls and stormwater pits for drainage.
PS603.06	Access Shower/Toilet/Change	FLOOR FINISH Ceramic tiled floor finish (tile joints be flush)	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Waterproofed floor with coved skirting; floor waste with falls in floor.
PS603.09	Laundry	FLOOR FINISH Ceramic tiled floor finish (tile joints be flush)	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Waterproofed floor with coved skirting; floor waste with falls in floor.
PS604 CANTEEN UNIT				
PS604.01	Canteen	FLOOR FINISH Industrial sheet flooring	-	FLOOR - OTHER Coved skirtings and solid plinths under benches



Floor

Schedule for Primary School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
PS604.11	Canteen Office / Store Room	FLOOR FINISH Industrial sheet flooring		FLOOR - OTHER Coved skirtings
PS604.21	Canteen Servery Covered Area	FLOOR FINISH Paved area	-	-
PS605 STORAGE UNIT				
PS605.01	Garden Store Room	FLOOR FINISH teel troweled concrete	-	FLOOR - OTHER Minimum threshold at door to enable equipment access.
PS605.11	Bulk Store Room	FLOOR FINISH Steel troweled concrete	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Minimum threshold at door to enable equipment access. Falls to outside.
PS605.21	Cleaning Supplies Store Room	FLOOR FINISH Steel troweled concrete	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Minimum threshold at door to enable equipment access. Falls to outside.
PS605.31	Cleaning Distributed Store Room	FLOOR FINISH Steel troweled concrete	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	-
PS607 ASSEMBLY COURT				
PS607.01	Assembly Area	FLOOR FINISH Broomed, coloured concrete to reduce glare	-	-
PS607.11	Flagpole	-	-	-
PS607.21	Assembly Zone	-	-	-
PS608 PEDESTRIAN CIRCULATION				
PS608.01	Paved Areas	FLOOR FINISH Broomed, coloured concrete to reduce glare; unit paving around trees (gravel is not to be used)	-	-
PS608.02	Paved Access	FLOOR FINISH Broom finished concrete	-	-
PS609 VEHICULAR CIRCULATION				
PS609.01	Service Roads	FLOOR FINISH Heavy Duty Service Roads - reinforced concrete Light Duty Service Roads - road metal base with bitumen flush seal	-	FLOOR - OTHER Heavy Duty Service Roads - Drainage to swale and perimeter sub soil drains or kerb and gutter with piped stormwater drains for poor soil conditions (CBR<5). Light Duty Service Roads - Kerb and gutter and stormwater drainage as necessary.
PS609.11	Bulk Waste Pad	FLOOR FINISH Reinforced concrete slab	-	-
PS609.21	Car Parking	FLOOR FINISH Asphaltic concrete on base course or reinforced concrete broomed finish.	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Drainage to swale and perimeter subsoil drains, or
PS609.31	Bus Zone	FLOOR FINISH Heavy duty reinforced concrete or asphaltic concrete.	-	FLOOR - OTHER Kerb and Gutter with piped stormwater drains for poor soil conditions (CBR<5). Monograde with lower side being the longer side is preferred option.
PS609.41	Bicycle Storage Area	FLOOR FINISH Student Waiting Zone: Broomed and coloured concrete.	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Where slope is between 1:50 and 1:30 drain to centre preferred.



Floor

Schedule for Primary School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
PS609.51	Crossovers	FLOOR FINISH Reinforced concrete slab	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Stormwater drainage as required
PS610 OPEN SPACES				
PS610.01	Free Play Area	FLOOR FINISH Turfed play area; spectator bank also turfed	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER High point in centre preferred. Where general fall around Free Play Area is too steep to permit this, fall should be across Free Play Area.
PS610.02	Passive Play/Open Areas	FLOOR FINISH Grass	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Preferred slope 1:8 and 1:4 maximum.
PS610.11	Street Frontage Zone	-	-	FLOOR - OTHER Massed plantings on slopes between 1:4 and 1:3. Slopes >1:3 may require retaining walls.
PS610.12	Active Zone	-	-	-
PS610.13	Passive Zone	-	-	-
PS610.14	Boundary Zone	-	-	-
PS610.15	Out of Bounds Zone	-	-	-
PS610.16	Special Function Zone	-	-	-
PS611 SERVICES				
PS611.01	Main Switchboard Cupboard	-	-	-
PS611.02	Distribution Board Cupboard	-	-	-
PS611.11	Services Zone	-	-	-
PS612 SITE				
PS612.01	Fencing	-	-	-
PS612.11	Waste Recycling	-	-	-
PS612.21	Signs	-	-	-
PS612.31	Site	-	-	-