



# Floor

Schedule for IO/IS/P School Rooms &amp; Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
<b>SSP430 HOME BASE UNIT (IO/IS/P)</b>				
SSP430.01	Home Base - IO	FLOOR FINISH C - Carpet finish	-	-
SSP430.02	Home Base - IS/P	FLOOR FINISH C - Carpet finish	-	-
SSP430.11	Home Base Store - IO/IS/P	FLOOR FINISH C - Carpet finish or to match adjacent area	-	-
SSP430.21	Withdrawal - IO/IS/P	FLOOR FINISH C - Carpet finish	-	-
SSP430.31	Practical Activities Area - IO/IS/P	FLOOR FINISH SVF - Foam backed sheet vinyl	-	-
SSP430.41	Personal Effects Storage - IO/IS/P	FLOOR FINISH SVF - Foam backed Vinyl to match adjacent area	-	-
<b>SSP501 LIBRARY</b>				
SSP501.01	Library Main Area	FLOOR FINISH C - Carpet finish	-	-
SSP501.11	Office/Workroom	FLOOR FINISH C - Carpet finish	-	-
SSP501.21	Communications Room	FLOOR FINISH ASV - Anti Static Vinyl	-	-
SSP501.32	KLA Resource Store	FLOOR FINISH SV - Sheet Vinyl(not foam backed)	-	-
<b>SSP502 SPECIAL PROGRAMS UNIT</b>				
SSP502.04	Special Programs Room - IO/IS/P	FLOOR FINISH C - Carpet finish	-	-
SSP502.16	Kitchenette - IO/IS/P	FLOOR FINISH SV - Sheet Vinyl(not foam backed)	-	-
SSP502.20	Special Programs Store	FLOOR FINISH C - Carpet finish or to match adjacent area	-	-
<b>SSP503 MULTIPURPOSE SPACE</b>				
SSP503.01	Multipurpose Space	FLOOR FINISH SVF - Foam backed Vinyl	-	-
SSP503.11	Chair Store	FLOOR FINISH CC - Steel Trowel Concrete finish	-	FLOOR OTHER Minimise threshold to enable movement of chairs



# Floor

## Schedule for IO/IS/P School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
SSP503.22	PE Store	FLOOR FINISH CC - Steel Trowel Concrete finish	-	FLOOR OTHER Minimise threshold to enable movement of chairs
SSP503.33	Sports Store	FLOOR FINISH CC - Steel Trowel Concrete finish	-	FLOOR OTHER Minimise threshold to enable movement of chairs
<b>SSP504 COVERED OUTDOOR LEARNING AREA (COLA)</b>				
SSP504.02	Covered Outdoor Learning Area	FLOOR FINISH Paved Area	-	FLOOR OTHER Central area to be relatively flat. Area to be graded remove surface water, away from central area
SSP504.07	Covered Outdoor Seating Area	FLOOR FINISH Paved Area	-	FLOOR OTHER Area to be graded remove surface water, away from central area
<b>SSP502 GAMES</b>				
SSP505.02	Games Court	FLOOR FINISH Asphaltic concrete preferred for resilience, non-slip, low maintenance and non-glare.	-	FLOOR OTHER Area to be graded remove surface water, away from central area Include 50mm wide court markings: Netball - green; Basketball - yellow; Volleyball - red
<b>SSP601 ADMINISTRATION UNIT</b>				
SSP601.01	Entry Vestibule	FLOOR FINISH C - Carpet finish	-	-
SSP601.11	Principal	FLOOR FINISH C - Carpet finish	-	-
SSP601.13	Deputy Principal	FLOOR FINISH C - Carpet finish	-	-
SSP601.15	Interview	FLOOR FINISH C - Carpet finish	-	-
SSP601.16	Interview/Office	FLOOR FINISH C - Carpet finish	-	-
SSP601.21	Clerical/Printing	FLOOR FINISH C - Carpet finish	-	-
SSP601.41	Security Store	FLOOR FINISH SV-Sheet Vinyl (not foam backed)	-	-
SSP601.51	Sick Bay	FLOOR FINISH SV-Sheet Vinyl (not foam backed)	-	-
SSP601.81	Entrance Zone	-	-	-

### SSP602 STAFF UNIT



# Floor

## Schedule for IO/IS/P School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
SSP602.01	Staff Room	FLOOR FINISH C - Carpet finish SV-Sheet Vinyl (not foam backed) to Kitchenette area	-	-
SSP602.21	Staff Room Annexe	FLOOR FINISH C - Carpet finish	-	-
SSP602.30	Staff Toilet	FLOOR FINISH CT- Ceramic tiles	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR OTHER Water Resistant Floor Grade floor to flow waste for drainage
<b>SSP603 STUDENT SERVICES UNIT</b>				
SSP603.02	Toilets	FLOOR FINISH CT- Ceramic Tiles	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR OTHER Coved skirting tiles at wall Well graded falls to floor waste.
SSP603.04	Hand Washing Outlets	-	-	-
SSP603.05	Drinking Facilities	FLOOR FINISH Water Resistant including adjacent area. Drinking Troughs not to be located in carpeted areas.	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR OTHER Falls to surface drainage if external. Falls to floor waste if internal
SSP603.10	Access Toilets/Shower	FLOOR FINISH CT- Ceramic tiles	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR OTHER Water Resistant Floor Coved skirting Grade floor to flow waste for drainage Tiles to have flush joints and not to have a bevelled edge.
SSP603.21	Laundry	FLOOR FINISH CT- Ceramic Tiles,	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR OTHER Coved skirting tiles at wall Falls to floor waste. Tiles are to have flush joints and not to have a bevelled edge.
SSP603.30	Seating	FLOOR FINISH Paved Area	-	FLOOR OTHER Area to be graded remove surface water
<b>SSP605 STORAGE UNIT</b>				
SSP605.01	Garden Store	FLOOR FINISH CC - Steel Trowel Concrete finish	-	FLOOR OTHER Threshold to be flush finished to enable wheeled equipment.
SSP605.11	Bulk Store	FLOOR FINISH CC - Steel Trowel Concrete finish	-	FLOOR OTHER Threshold to be flush finished to enable wheeled equipment.
SSP605.21	Cleaning Supplies Store	FLOOR FINISH CC - Steel Trowel Concrete finish	-	FLOOR OTHER Threshold to be flush finished to enable wheeled equipment.
SSP605.31	Cleaning Distributed Store	FLOOR FINISH ISF - Industrial sheet flooring.	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR OTHER threshold to be flush finished to enable wheeled equipment etc. Grade floor to floor waste where provided
SSP605.41	General Store	FLOOR FINISH CC - Steel Trowel Concrete finish	-	FLOOR OTHER Threshold to be flush finished to enable wheeled equipment.
<b>SSP607 ASSEMBLY COURT</b>				
SSP607.01	Assembly Area	FLOOR FINISH Type 1 - Broom finished coloured concrete Type 2 - RFS, Poured Rubber Softfall	-	FLOOR OTHER falls to surface drainage if external.



# Floor

## Schedule for IO/IS/P School Rooms & Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
SSP607.11	Flagpole	-	-	-
SSP607.21	Assembly Zone	-	-	-
<b>SSP608 PEDESTRIAN CIRCULATION</b>				
SSP608.01	Paved Areas	FLOOR FINISH Broomed, coloured concrete to reduce glare. Unit paving around trees. Gravel is not allowed.	-	FLOOR OTHER falls for surface drainage.
SSP608.02	Paved Access	FLOOR FINISH Broom finished concrete	-	FLOOR OTHER Areas to be graded to provide drainage while maintaining wheelchair accessible grades
<b>SSP609 VEHICULAR CIRCULATION</b>				
SSP609.01	Service Roads	FLOOR FINISH Service Road (heavy Duty) - reinforced concrete Service Roads (Light Duty) - road metal base with bitumen flush seal Service Road ( Access) - road metal base with bitumen flush seal	-	FLOOR - OTHER Heavy Duty Service Roads - Drainage to swale and perimeter sub soil drains or kerb and gutter with piped stormwater drains for poor soil conditions (CBR<5). Light Duty Service Roads - Kerb and gutter and stormwater drainage as necessary.
SSP609.11	Bulk Waste Pad	FLOOR FINISH Reinforced concrete slab	-	-
SSP609.21	Car Parking	FLOOR FINISH Asphaltic concrete on base course or reinforced concrete broomed finish.	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Drainage to swale and perimeter subsoil drains, or Kerb and Gutter with piped stormwater drains for poor soil conditions (CBR<5). Monocore with FLOOR - OTHER Stormwater drainage as required
SSP609.51	Crossovers	FLOOR FINISH Reinforced concrete slab to local council requirements	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR - OTHER Stormwater drainage as required
SSP609.61	Student Set Down	FLOOR FINISH Heavy Duty reinforced Concrete, Waiting zone broom finish	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR OTHER Areas to be graded to provide drainage while maintaining wheelchair accessible grades
SSP609.62	Porte Cochere	FLOOR FINISH Heavy Duty reinforced Concrete, Waiting zone broom finish	FLOOR WASTE Floor waste(s) are to be included with falls in floor.	FLOOR OTHER Areas to be graded to provide drainage while maintaining wheelchair accessible grades
<b>SSP610 OPEN SPACES</b>				
SSP610.01	Free Play Area	FLOOR FINISH Turfed area	-	FLOOR OTHER Preferred fall for drainage 1:30 - 1:40. Some areas may require a greater degree of fall. High point in centre preferred.
SSP610.02	Passive Play/Open Areas	FLOOR FINISH Grassed	-	FLOOR OTHER Planted beds should be in trample proof locations and kept to a minimum.
SSP610.11	Street Frontage Zone	-	-	-
SSP610.12	Active Zone	-	-	-
SSP610.13	Passive Zone	-	-	-



# Floor

Schedule for IO/IS/P School Rooms &amp; Spaces

ID	ROOM/SPACE NAME	FF	FW	OTH
SSP610.14	Boundary Zone	-	-	-
SSP610.15	Out of Bounds Zone	-	-	-
SSP610.16	Special Function Zone	-	-	-
<b>SSP611 SERVICES</b>				
SSP611.01	Main Switchboard Cupboard	-	-	-
SSP611.02	Distribution Board Cupboard	-	-	-
SSP611.11	Services Zone	-	-	-
<b>SSP612 SITE</b>				
SSP612.01	Boundary Fencing	-	-	-
SSP612.21	Signs	-	-	-